

PROVIDED EQUIPMENT

1. 150# R.F.S.O. FLANGE W/ 2" NPT FOR VENT 2. 4"ø FTG. FOR GAUGE WITH PLUG TYP. BOTH MANWAYS

3. VELOCITY HEAD DIFFUSION BAFFLE

4. WEAR PLATE

5. SEDIMENT CHAMBER

6. UNDERFLOW BAFFIF 7. SLUDGE BAFFLE

8. STRIKER PLATES

9. PARALLEL CORRUGATED PLATE COALESCER. CORELLA PVC PLATES
10. OIL/WATER SEPARATOR CHAMBER
11. 2"Ø FTG. FOR LEAK DETECTION

12. OUTLET DOWNCOMER

13. 24"Ø MANWAY WITH BOLT-ON EXTENSION SHIPPED LOOSE

14. 4"ø FTG. FOR OIL PUMPOUT W/ INTERNAL PIPE INSTALLED

& RISER PIPE SHIPPED LOOSE

15. 2"ø FTG. FOR LEVEL SENSOR W/ RISER PIPE SHIPPED LOOSE


16. LIFTING LUG

17. 2"ø FTG. FOR VENT TYP. BOTH MANWAYS

2. ALL VENT PIPING BY INSTALLER

GENERAL SPECIFICATIONS

3. 15000 VOLT SPARK TEST PROVIDED AT FACTORY




NOTE:

ALL RIGHTS RESERVED. THIS DRAWING OR ANY PART THERE OF MUST NOT BE REPRODUCED IN ANY FORM WITH OUT THE WRITTEN PERMISSION

OF HIGHLAND TANK

HIGHLAND TANK SHALL BE RESPONSIBLE ONLY FOR ITEMS INDICATED ON THIS FABRICATION DRAWING UNLESS OTHERWISE NOTED. CUSTOMER IS RESPONSIBLE FOR VERIFYING CORRECTNESS OF SIZE / LOCATION OF FITTINGS , ACCESSORIES & COATINGS SHOWN ON THIS DRAWING

ELEVATION



REVISIONS